



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1973

CONSERVATION DIVISION
Wichita, Kansas

8-20-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: R. P. Nixon,

Complete Address: P. O. Box #589, Russell, Kansas.

Lease Name: Henry Well No. 2

Location: NE-NE-SW Sec. 35 Twp. 3 Rge. (E)(W) 24

County: Norton Total Depth 3755 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

255'--8 5/8" Surface casing, cement circulated.

3751'--5 1/2" Production casing cemented on bottom with 100 Sx. Hole in casing @ 1600'. 35 rods left in hole and tubing backed off @ seating nipple. Hole sanded off @ 2900'. Du

Dump 5 Sx. cement with dump bailer @ 2900'. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent