

15-137-19013-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 33-22

LOCATION SE NE SW

SEC. 35 TWP. 3 RGE. 24

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Henry

Operator H. Gore Address Wichita, Kans

Field _____ County Nowton

Total Depth 3754 Feet.

Plugging Contractor R & S Pipe Pulling

Plugging Contractor's License No. 1

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 256' circulated with cement - 5 1/2" at 3744 with
100 sax cement behind.

Filled with sand to 3730', set 4 sax cement with dump bailer,
pulled 3055' 5 1/2", mud to 255', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

STATE CORPORATION COMMISSION

MAY 25 1954

CONSERVATION DIVISION
Wichita, Kansas

E. J. [Signature]
District Conservation Agent

Date 5-20-54

PLUGGING
FILE SEC 35 T 3 R 24W
BOOK PAGE 33 LINE 22