

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-137-00513-00-00

JUL 7 1966
7-7-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. P. Nixon Operations, Incorporated,

Complete Address: 754 E. Wichita, Russell, Kansas.

Lease Name Henry Well No. 1

Location SE-NE-NW ^{loc ab} Sec. 35 Twp. 3 Rge. (E) (W) 24

County Norton (Attempted Washdown TD 700'
(Original) Total Depth 3754'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: ATTEMPTED WASHDOWN

Plugging Contractor: United Oil Well Cementing, Incorporated,

Address: Box #464, Eldorado, Kansas. License No.

Operation Completed: Hour 6:30PM Day 29 Month 6 Year 1966

The Above well was plugged as follows:

263'--8 5/8" Surface pipe, cement circulated.

This hole was an attempted washdown. Junk was encountered in the hole

and 2 joints of 5 1/2" casing were lost @ 700'. Hole was abandoned there.

Hole was originally plugged off with sand bridge from 3754' to 3730' and

3 Sx. cement from 3730' to 3710' then mud from 3710' to 270'. In wash-

ing down heavy gel was circulated to 700'.

Found fluid @ 150', set rock bridge and filled hole to bottom of cellar

with 50 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 7/7/66

INV. NO. 3528-W