

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-137-00708-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
11-4-74

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Lawson Well No. 8

Location CEL-SE/4 Sec. 36 Twp. 3 Rge. (E) (W) 24

County Norton Total Depth 3793'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address P. O. Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 23 Month 10 Year 1974

The above well was plugged as follows:

263'--8 5/8" Surface casing, cement circulated with 135 Sx.  
3783'--5 1/2" Production casing cemented on bottom with 100 Sx. (Open hole Completion).  
Sanded well back to 3770' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(1115') and squeezed well initially with 5 sacks hulls and 15 sacks gel followed with  
90 Cu. Ft. cement from 1160' to 900' then 15 sacks gel from 900' to 300' and followed  
with 30 Cu. Ft. cement from 300' to 225' then 5 sacks gel from 225' to 25' and finally  
10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-300#. Final  
Shut-in pressure-100#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/4/74

INV. NO. 235-W