

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Lawson Well No. 7

Location CSE/L Sec. 36 Twp. 3 Rge. (E) (W) 24

County Norton Total Depth 3782'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address P. O. Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00 PM Day 23 Month 10 Year 1974

The above well was plugged as follows:

260'--10 3/4" Surface casing, cement circulated with 135 Sx.
3781'--7" OD Production casing cemented on bottom with 100 Sx. (Open hole completion).

Sanded well back to 3750' and set 6 Sx. cement with dump bailer. Pulled 7" casing
(1025') and squeezed well initially with 5 sacks hulls and 15 sacks gel followed with
40 Cu. Ft. cement from 1200' to 900' then 21 sacks gel from 900' to 270' and followed
with 40 Cu. Ft. cement from 270' to 200' then 7 sacks gel from 200' to 25' and finally
10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-450#.

Final shut-in pressure-200#. (Mudding and cementing by Allied cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: K. L. Dickels
Well Plugging Supervisor

INVOICED

DATE 11/4/74

INV. NO. 234-w