

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-137-00680-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
11-21-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Lawson Well No. 2

Location SW-SW-SE Sec. 36 Twp. 3 Rge. (E) (W) 24

County Norton Total Depth 3791'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:15 PM Day 23 Month 10 Year 1974

The above well was plugged as follows:

284'--8 5/8" Surface casing, cement circulated with 150 Sx.
3790'--5 1/2" Production casing cemented on bottom with 125 Sx. (Open hole completion).

Sanded well back to 3775' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1115') and squeezed well initially with 5 sacks hulls and 15 sacks gel followed with
90 Cu. Ft. cement from 1160' to 900' then 15 sacks gel from 900' to 300' and followed
with 30 Cu. Ft. cement from 300' to 225' then 5 sacks gel from 225' to 25' and
finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-
350#. FSIP-150#. (Mudding and cementing by Allied Cementing Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dechale
Well Plugging Supervisor

INVOICED

DATE 11/4/74

INV. NO. 233-W