

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-137-00640-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NE

SEC. 35 TWP. 3 RGE. 24 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease Schoen "A"

Operator Jones Shelburne Farmer Address Russell, Kans

Field _____ County Norton

Total Depth 3791 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 278' circulated with cement - 5 1/2" at 3789' with 75 sax
cement behind - perforated at 3781'.

Filled with sand to 3770', set 4 sax cement with dump bailer,
pulled 1440' 5 1/2" - mud to 278', set rock and 15 sax cement, mud to
35', set rock and 10 sax cement to bottom cellar.

E. P. [Signature]

District Conservation Agent

STATE CORPORATION COMMISSION

Date 10-7-54

10-12-54

PLUGGING
FILE SEC. 35 T. 3 R. 24W
BOOK PAGE 22 LINE 10