

15-137-00514-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1973
CONSERVATION DIVISION
Wichita, Kansas

820-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name R. P. Nixon,

Complete Address Box #589, Russell, Kansas.

Lease Name Henry Well No. 2

Location NE-NE-SW Sec. 35 Twp. 3 Rge. (E) (W) 24

County Norton Total Depth 3755'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 12:00M Day 17 Month 8 Year 1973

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated.
3751'--5 1/2" Production casing cemented on bottom with 100 Sx. Hole in casing @ 1600'.
35 rods left in hole and tubing backed off @ seating nipple. Hole sanded off @ 2900'.
Ran 5 Sx. cement @ 2900' with dump bailer. Pulled 5 1/2" casing (1030') and squeezed
well initially with 5 sacks hulls and 12 sacks gel and followed with 110 Cu. Ft.
cement from 1150' to 825' then 13 sacks gel from 825' to 300' and followed with 13
sacks gel from 300' to 225' then 5 sacks gel from 225' to 25' and finally 10 Cu. Ft.
cement from 25' to bottom of cellar. Maximum pump-in pressure-250#. Final shut-in
pressure-150#. (Mudding and cementing operations by Allied Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dickels
Well Plugging Supervisor

DATE 8/22/73
INV. NO. 7800-u