

5-12-88 15-137-00690-00-00

6040885

API NUMBER 15-

3-54

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW _____, SEC. 36, T 3 S, R 24 W,
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135
Operator: John O. Farmer
Name & Address: Box 352
Russell, Ks. 67665

Lease Name Lawson A Well # 7
County Norton 121.88
Well Total Depth 3750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280' w/125

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 12 Month: May Year: 19 88

Plugging proposal received from Lawrence 'Slim' Eichman

(company name) John O. Farmer (phone) _____

were: 5 1/2" casing set at 3742' w/75 sks cement. Perfs at 3742' to 3750'.

Sq. at 1530' w/300 sks. Perf casing at 1300'

Ordered 250 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1988
7-6-88

CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45AM Day: 12 Month: May Year: 1988

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 175 sks cement w/1/4# F.C. plus

6 sks Hulls mixed in cement. Max Psi 300# Shut in 200#.

Pumped in 8 5/8" casing 75 sks cement w/1/4# F.C. Max Psi 500# Shut in 300#.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If ~~not~~ observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)

DATE 7-7-88

INV. NO. 21211

Dennis L. Hamel