

5-12-88 15-137-00528-06-00

6 040883

API NUMBER 15- 3-1954

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2S/2 NE, SEC. 36, T 3 S, R 24 W/
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Stapleton Well # 9

Operator: John O. Farmer

County Norton 120.71

Name & Address Box 352

Well Total Depth 3714 feet

Russell, Ks. 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280' w/125

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 12 Month: May Year: 19 88

Plugging proposal received from Lawrence 'Slim' Eichman

(company name) John O. Farmer (phone) _____

were: 5 1/2" casing set at 3706' w/75 sks cement. O.H. at 3706' to 3714'. Holes in casing from 1735' - 2849' and 1300' - 1425'.

Ordered 300 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15AM Day: 12 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 175 sks cement w/1/4# F.C. plus 4 sks Hulls mixed in cement. Max Psi 1000# Shut in 600# Pumped in 8 5/8" casing 75 sks cement w/1/4# F.C. plus 1 sk Hulls. Max Psi 500# Shut in 300#.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1988

7-6-88

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(If you observe this plugging.)

DATE 7-7-88
INV. NO. 21215

Signed Dennis L. Hamel (TECHNICIAN)
Dennis Hamel