

5-12-88 15-137-00299-00-00

6-040887

API NUMBER 15- 5-53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NW, SEC. 36, T 3 S, R 24 W/-
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135
Operator: John O. Farmer
Name & Address: Box 352
Russell, Ks. 67665

Lease Name Lawson A Well # 1
County Norton 123.18
Well Total Depth 3790 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00AM, Day: 12 Month: May Year: 19 88

Plugging proposal received from Lawrence 'Slim' Eichman

(company name) John O. Farmer (phone) _____

were: 5 1/2" casing set at 3779' w/100 sks cement. Perfs at 3779' to 3790'. Holes in casing at 1600' and 280'. Perf Dakota at 1350'. Rods and tubing at 2600'.
Ordered 250 sks 65/35 Poz 10% Gel w/1/4" F.C. plus 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1988

7-6-88

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 PM Day: 12 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 125 sks cement w/1/4" F.C. plus 4 sks

Hulls mixed in cement. Max Psi 1000# Shut in 900#. Pumped in 8 5/8" casing 75 sks cement w/1/4" F.C. plus 1 sks Hulls. Max Psi 200# Shut in 150#.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (observe this plugging.)

DATE 7-7-88

INV. NO. 21209

Signed Dennis L. Hamel (TECHNICIAN)