

2-13
4-032207

15-137-00516-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1954

C E2 NE /4 SEC. **35** , **03** , **24 W**
3960 feet from S section line
660 feet from E section line

Operator license# **5135**

Lease: **Schoen "A"** Well # **4**

Operator: **John O. Farmer**

County: **Norton** 122.91

Address: **P.O. Box 352**
Russell, Kansas 67665

Well total depth **3782** feet
Conductor Pipe: **0** inch @ **0** feet
Surface pipe 8 5/8 Inch @ **280** feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: **Allied Cement Company** License# _____

Address: **Russell, Kansas 67665**

Company to plug at: Hour: **A.M.** Day: **13** Month: **February** Year: **1997**

Plugging proposal received from: **Duane Eichman**

Company: **John O. Farmer** Phone: _____

Were: **Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.**
Webb's Water Truck Service.
Order work string.

MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997
MAR 03 1997

2-28-97

Plugging Proposal Received by: **Carl Goodrow**

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: **11:45 A.M.**, Day: **13**, Month: **February**, Year: **1997**

Actual plugging report: **8 5/8" set at 280' w/125 sxs cwc. 5 1/2" set at 3782' with 75 sxs. O.H. 3782' - 3788'. PBTD 3788'. Squeezed at 1730' w/200 sxs. Critical area control shots at 2040' and 1300'. Ran tubing to 3000'. Pumped 70 sxs cement blend with 200# hulls. Pulled tubing to 2000'. Circulated cement with 160 sxs and hulls. Pulled tubing. Topped off 5 1/2" w/20 sxs. Used total of 250 sxs with 450# hulls. Squeezed 8 5/8" w/50 sxs cement blend. Plug complete.**

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

INVOICED
DATE **MAR 03 1997**
INV.NO. **47684**
[] observe the plugging.

Carl Goodrow
(agent)