

7-3115-137-00687-00-00

6 041315

API NUMBER 15-10-20-53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

G S/2 NW, SEC. 36, T 3 S, R 24 W/E

3300 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Lawson "A" Well # 3

Operator: John O. Farmer Inc.

County Norton 122.94

Name & Address

P.O. Box 352

Well Total Depth 3783 feet

Russell, Kansas 67665

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 280' w/125 sx.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Kansas 67665

Company to plug at: Hour: 11:45A.M. Day: 31 Month: 7 Year: 19 91

Plugging proposal received from Duane Eichman

(company name) J.O. Farmer (phone)

were: 5 1/2" casing set at 3779' w/75 sks. cement. O.H. to 3783'. Perf. base

dakota at 1350'. Casing squeezed @ 2115' - 2630' w/450 sx. cement.

Ordered 350 sks. 60/40 poz. 10% gel. w/1/4 lb. flocele plus 500# hulls.

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45A.M. Day: 31 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing w/25 sks. cement w/1/4 lb. flocele plus

pumped in additional 250 sks. cement w/1/4 lb. flocele and 400# hulls mixed in cement.

Max. 400 lb. S.I. 100 lb. Pumped in 8 5/8" casing w/75 sks. cement w/1/4 lb. f.c.

and 100# hulls mixed in cement. Max. 200 lb. S.I. 100 lb.

Check casing cement: down @ 400', filled to surface w/redi-nix cement

RECEIVED

STATE CORPORATION COMMISSION

AUG 21 1991

8-21-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did not) observe this plugging.

DATE 8-28-91

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 32866