

5-12-88 15-137-00686-00-00

6 040884

API NUMBER 15- 8-83

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SW NW, SEC. 36, T 3 S, R 24 W/L  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Lawson A Well # 2

Operator: John O. Farmer  
Name & Address Box 352

County Norton 123.57

Well Total Depth 3802 feet

Russell, Ks. 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 280 w/

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 12 Month: May Year: 1988

Plugging proposal received from Lawrence 'Slim' Eichman

(company name) John O. Farmer (phone) \_\_\_\_\_

were: 5 1/2" casing set at 3791' w/100 sks cement.

Perfs at 3791' to 3802'. Sq hole in casing 1600' w/150 sks. Hole in casing at 1160'.

Ordered 250 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:45AM Day: 12 Month: May Year: 19 88

ACTUAL PLUGGING REPORT

Pumped in 5 1/2" casing 175 sks cement w/1/4# F.C. plus 4 sks Hulls mixed in cement.

Max Psi 800# Shut in 300#. Pumped in 8 5/8" casing 75 sks cement w/1/4# F.C. plus

1 sk Hulls. Max Psi 300# Shut in 100#.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 1988  
77-6-88  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED** serve this plugging.

DATE 7-7-88

Signed Dennis L. Hamel  
(TECHNICIAN)

INV. NO. 21210