

5-7 15-137-00083-00-00 90 R

6 031541

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1954
W/2 SE, SEC. 36, T 3 S, R 24 (W)
1320 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Charles Lawson Well # 5

Operator: Gore Oil Co.
Name & Address: P.O. Box 2757
Wichita, Kansas 67201-2757

County Norton 122.72
Well Total Depth 3776 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B J Services License Number _____
Address Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 7 Month: 5 Year: 19 91

Plugging proposal received from Scott

(company name) Gore Oil Co. (phone) _____

were: 8 5/8 set @ 259' w/135 sx. 5 1/2 set @ 3774' w/100 sx. O.H. 3774'-76'

Order 400 sx. 65/35 poz. 10% Gel. 400# Hulls. 13 sx. Gel. B.J. Services

Webb and Gore water trucks.

Ran wire line to T.D., Hole open. Shots @ 2050' and 1275'

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 P.M. Day: 7 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 5 1/2 casing w/100 sx. cement blend w/200# Hulls

mixed in followed with 13 sx. Gel. Followed with 175 sx. cement blend with

200# Hulls mixed in to max. PSI 1000#. Close in PSI 900#. Squeezed

8 5/8 w/100 sx. cement blend w/200# Hulls mixed in to max. PSI 400#.

Close in PSI 300#. Plug complete

RECEIVED
STATE CORPORATION COMMISSION
520-91
MAY 27 1991

Remarks: **INVOICED** Additional description is necessary, use BACK of this form.

I (did / did not) observe this plugging.

DATE 5-29-91
REV. NO. 31939

File S

Signed Carl Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas