

5-7 15-137-00679-00-00

87
R

6 031542

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1953
NW SE, SEC. 36, T 3 S, R 24 W/E

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
1980 feet from E section line

Operator License # 5552

Lease Name Charles Lawson Well # 1

Operator: Gore Oil Company

County Norton 122.03

Name & Address P.O. Box 2757

Well Total Depth 3755' feet

Wichita, Kansas 67201-2757

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 265

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B J Services License Number _____

Address Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 7 Month: 5 Year: 19 91

Plugging proposal received from Scott

(company name) Gore Oil Company (phone) _____

were: 10 3/4 set @ 265' w/200 sx. 7" set @ 3720' w/100 sx. 5 1/2 liner set

3689'-3752' w/35 sx. O.H. 3752'-3755' Order 400 sx. 65/35 poz. 10% Gel.

400# Hulls. 23 sx. Gel. B J Services, Webb and Gore water trucks.

Ran wire line to T.D. Hole open, shots @ 2050' and 1275'

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 P.M. Day: 13 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 7" w/100 sx. cement blend w/200# Hulls.

Mixed in followed w/23 sx. Gel. Followed with 200 sx. cement blend w/100# Hulls

mixed in to max. PSI 900#. Close in PSI 600#. Squeezed 10 3/4" w/100 sx.

cement blend w/100# Hulls mixed in to max. PSI 450#. Close in PSI 350#

Plug complete.

RECEIVED

STATE CORPORATION COMMISSION

5-20-91
MAY 20 1991

Remarks: _____

INVOICED

(I did / did not observe this plugging.)

CONSERVATION DIVISION
Wichita, Kansas

DATE 5-29-91

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 31937