

11-14

156

4 - 041342

15-137-00675-00-00

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 4-1-54

C SW /4 SEC. 36, 03 S, 24 W
1320 feet from S section line
3960 feet from E section line

Operator license# 5135

Lease Lawson well # B-6

Operator: J.O. Farmer

County Norton

Address: P.O. Box 352
Russell, Kansas 67665

Well total depth 3790 feet ^{123.17}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 280 feet
w/125 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 14 Month: November Year: 91

Plugging proposal received from: Duane Eichman

Company: J.O. Farmer Phone: 913-434-7237

Were: 5 1/2" casing at 3788' w/75 sxs. Perf. 3788' - 95'.
Perf. @ 2075'. Perf. @ 1380'. Ordered 400 sxs. 60/40 pozmix - 10% gel.
with 1/4# F.C. and 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All], Part], None]

Completed: Hour: 12:30P.M, Day: 14, Month: November, Year: 91

Actual plugging report: Pumped in 5 1/2" casing. 325 sxs. 60/40
pozmix - 10% gel. with 1/4# flocele plus 3 sxs. hulls. Max. 800# P.S.I.
S.I. 200# P.S.I. Pumped in 8 5/8" S.P. 75 sxs. 60/40 pozmix
10% gel. with 1/4# flocele plus 100 sxs hulls. Max. 400# P.S.I.
S.I. 100# P.S.I. Perf. anhy. @ 2075'. Perf. base of Dakota @ 1380

NOV 25 1991

11-2591

Remarks:

INVOICED

I did] did not] observe the plugging.

Dennis L. Hamel

DATE 12-5-91

INV. NO. 33956

J.O. Farmer

(agent)
Form CP-2/3