

4-032141

15-137-00670-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

4-1

API Number: 15- - 1953

NE NE SW /4 SEC. 36, 03, 24 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 5135

Lease: Lawson Well # B-1

Operator: John O. Farmer, Inc.

County: Norton

Address: P.O. Box 352  
Russell, Kansas 67665

Well total depth 3777 <sup>122.75</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 290 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 1 Month: April Year: 1996

Plugging proposal received from: Duane Eichman - Dennis Hamel

Company: John O. Farmer, Inc. Phone:

Were: Order 350 sxs 60/40 pozmix - 10% gel - 1/4# flocele - 500# hulls mixed in.  
Work string. Poe Well Service. RECEIVED  
KANSAS CORPORATION COMMISSION

APR 08 1996

CONSERVATION DIVISION  
WICHITA, KS

4-8-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:45 P.M., Day: 1, Month: April, Year: 1996

Actual plugging report: 8 5/8" set at 290' cwc with 125 sxs. 7" set at 3773' with 75 sxs cwc. O.H. 3773' - 3777'. Ran tubing to 2050' circulated cement blend to surface with 300 sxs with 400# hulls mixed in. Squeezed 8 5/8" with 50 sxs cement blend and 100# hulls. Max. P.S.I. 500#. Held. Critical area control shots at 2000' and 1300'. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ ] did not [ ] observe the plugging.

INVOICED  
DATE APR 18 1996  
INV. NO. 45343

Carl Goodrow  
(agent)  
Form CP-2/3