


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

15-153-05135-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rawlins County. Sec. 13 Twp. 2s Rge. 36 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW NE  
Lease Owner Westheimer - Neustadt, Shear  
Lease Name Cahoj Well No. 1  
Office Address Box 974, Ardmore, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 22 19 58  
Application for plugging filed September 22 19 58  
Application for plugging approved September 22 19 58  
Plugging commenced September 22 19 58  
Plugging completed September 23 19 58  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation none Depth to top Bottom Total Depth of Well 5090 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1. Set bottom plug at depth of 600 feet. Spotted 20 sacks cement. Filled hole with heavy mud to depth of 315 feet.
2. Set center plug at depth of 315 feet. Dumped in about 1/3 sack hulls. Spotted 20 sacks cement. Filled hole to within 40 feet of top with heavy mud.
3. Set top plug at depth of 40 feet. Dumped in about 1/3 sack hulls. Spotted 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Oil Well Cementing Co.  
Address Hill City, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Richard G. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) *Richard G. Smith*

2934 Euclid, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 58

*Attamas Hising*  
Notary Public.

My commission expires 1-24-59

Rec'D  
9-30-58

PLUGGING  
FILE SEC 13 T 2 R 36W  
BOOK PAGE 132 LINE 40

15-153-05135-00-00

DRILLERS' LOG

Westheimer, Neustadt, & Shear

Cahoj No. 1

NW NW NE Sec. 13 - 2s - 36w  
Rawlins County, Kansas

Elevation: 3297 GL  
3305 DF  
3307 KB

Rotary Total Depth: 5090

Commenced: September 12, 1958  
Completed Drilling with Rotary: September 22, 1958  
Casing: 9-5/8 @ 317

Contractor: Miami Petroleum Co.  
Box 2040  
Abilene, Texas

FORMATION

DEPTH

shale	0-1400
sand and shaley sand	1400-1850
shale and sandy shale	1850-2750
shale	2750-3020
anhydrite	3020-3040
shaley anhydrite	3040-3180
anhydrite	3180-3220
lime and shale	3220-4160
lime	4160-4280
shale	4280-4320
lime	4320-4550
shale	4550-4612
lime and shale	4612-4760
shale and sand	4760-4930
cherty lime and dolomite	4930-5030
dolomite	5030-5090

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1958

REGISTRATION DIVISION

9-30-58

PLUGGING

FILE SEC 13 T 2 R 36W  
BOOK PAGE 132 LINE 40