


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

RAWLINS

County. Sec. 7 Twp. 2S Rge. 36 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW/SW/SW
Lease Owner Miami Petroleum Company, Inc.
Lease Name Fred Brumm "F" Well No. 1
Office Address P.O. Drawer 2040, Abilene, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 3 19 59
Application for plugging filed herewith 19 61
Application for plugging approved Verbal and written- October 19 61
Plugging commenced 10/13 19 61
Plugging completed 10/20 19 61
Reason for abandonment of well or producing formation Reached economic limits



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production March 21 19 61
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Topeka Depth to top 4220 Bottom 4246 Total Depth of Well 5082 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	Oil & gas	4220	4246	5 1/2"	4600'	2190'
				9-5/8"	349'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 4100 ft. with sand. Dumped 4 sacks cement. Pulled pipe to 500 ft. Pumped in 50 sacks mud. Pulled pipe to 350 ft. pumped in 25 sacks cement. Pulled pipe - dumped in 10 sacks cement on top.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1961
CONSERVATION DIVISION
Wichita, Kansas
11-20-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Central Pipe Pulling Company
Address 1416 Coolidge, Great Bend, Kansas

STATE OF Texas, COUNTY OF Taylor, ss.
Jack Stivers (employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Stivers
P. O. Drawer 2040, Abilene, Texas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November 19 61

My commission expires June 1, 1963
Marjorie D. Lubbering Notary Public.
Taylor County, Texas

15-153-05132-00-00

MIAMI PETROLEUM COMPANY, INC.

Fred Brumm "F" #1
SW/SW/SW, Sec. 7, T-2S, R-36W
Rawlins County, Kansas

Drillers Log

<u>Depth</u>		<u>Formation</u>
<u>From</u>	<u>To</u>	
0	325	Shale & Sand
325	1025	Shale
1025	2175	Shale, Sand & Lime
2175	2540	Shale & Broken Lime Shell
2540	3010	Shale, Lime & Sand
3010	3255	Lime, Chert, Shale & Sand
3255	3480	Shale, Lime & Chert
3480	4239	Lime & Shale
4239	4255	Lime
4255	4385	Lime & Shale
4385	4390	Lime
4390	4435	Lime & Shale
4435	4443	Lime
4443	4694	Shale & Lime
4694	4755	Lime
4755	4815	Lime & Shale
4815	4893	Lime, Sand & Chert
4893	4950	Sand & Chert
4950	5001	Lime, Shale & Sand
5001	5085 T.D.	Lime & Chert

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1961

CONSERVATION DIVISION
Wichita, Kansas

11-20-61