

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-137-00679-00-00

API NUMBER n/a

LEASE NAME Charles Lawson

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

~~990 1980~~ Ft. from S Section Line

~~990 1980~~ Ft. from E Section Line

SEC. 36 TWP. 3s RGE. 24 (E) (X) (W)

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757, Wichita, KS 67201-2757

PHONE# (316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

COUNTY Norton

Date Well Completed 8-53

Plugging Commenced 5-7-91

Plugging Completed 5-13-91

The plugging proposal was approved on 4-30-91 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? See CP-1

Producing Formation Arbuckle Depth to Top 3752' Bottom 3755' T.D. 3755'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil, water	0	265	10 3/4"	265'	0'
		0	3720	7"	3720'	0'
		3689'	3752'	5 1/2"	63'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforate 7" at 2050' and 1275'. Pumped down 7" 100 sx 65/35, 10% gel, 200# hulls, 21 sx gel, 308 sx 65/35, 10% gel, 350# hulls. Maximum pressure 900 psi. Pumped down 10 3/4"-7" annulus 100 sx 65/35, 10% gel. Maximum pressure 450 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Services License No. _____

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 91



REBECCA K. CRAWFORD
State of Kansas
My Appt. Exp. 7-95

Rebecca K. Crawford
Notary Public

My Commission Expires: 1-7-95