

15-137-00684-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER n/a

LEASE NAME Charles Lawson

WELL NUMBER 6

1980 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 36 TWP. 3s RGE. 24 ~~(S)XXX(W)~~

COUNTY Norton

Date Well Completed 3-54

Plugging Commenced 5-7-91

Plugging Completed 5-7-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757, Wichita, KS 67201-2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-30-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? See CP-1

Producing Formation Arbuckle Depth to Top 3761' Bottom 3764' T.D. 3764'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil, water	0	243	8 5/8"	243'	0'
		0	3761	5 1/2"	3761'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate 5 1/2" at 2050' and 1275'. Pump down 5 1/2" 100 sx 65/35, 10% gel, 13 sx gel, 175 sx 65/35, 10% gel w/100# hulls. Maximum pressure 800 psi. Pump down 8 5/8"-5 1/2" annulus 100 sx 65/35, 10% gel, 200# hulls. Maximum pressure 450 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Services License No. RECEIVED STATE CORPORATION COMMISSION

Address Hays, KS 5-23-91

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company MAY 23 1991

STATE OF Kansas COUNTY OF Sedgwick, ss. CONSERVATION DIVISION Wichita, Kansas

Scott W Scheuerman (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 91

STATE OF KANSAS
REBECCA K. CRAWFORD
Notary Public
My Appt. Exp. 1-7-95

Rebecca K Crawford
Notary Public

My Commission Expires: 1-7-95