

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-137-00683-00-00

API NUMBER n/a

LEASE NAME Charles Lawson

WELL NUMBER 5

1320 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 36 TWP. 3s RGE. 24 (E)(W)

COUNTY Norton

Date Well Completed 2-54

Plugging Commenced 5-7-91

Plugging Completed 5-7-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757, Wichita, KS 67201-2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-30-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? See CP-1

Producing Formation Arbuckle Depth to Top 3774' Bottom 3776' T.D. 3776'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil, water	0	259	8 5/8"	259'	0'
		0	3774	5 1/2"	3774'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate 5 1/2" at 2050' and 1275'. Pumped down 5 1/2" 100 sx 65/35, 10% gel, 13 sx gel, 175 sx 63/35, 10% gel w/200# hulls. Maximum pressure 1000 psi. Pumped down 8 5/8"-5 1/2" annulus 100 sx 65/35, 10% gel. Maximum pressure 400 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

Name of Plugging Contractor B. J. Services License No. \_\_\_\_\_

Address Hays, KS

MAY 23 1991

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.


5-23-91

Scott W Scheuerman (Employee of Operator) ~~XXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 91



Rebecca K. Crawford  
Notary Public

My Commission Expires: 1-7-95

COMPANY:

CONTRACTOR:

FARM:

LOCATION:

COMMENCED:

COMPLETED:

15-137-00683-00-00

Harry Gore

Empire Drilling Company

Lawson #5

CWL SE $\frac{1}{4}$ , Sec. 36-3-24  
Norton County, Kansas

1-29-54

2-10-54

*Productivity: 215*

0	to	278	Sand, Shales and shells
278	to	1125	Shale and shells
1125	to	1450	Shale, sand and shells
1450	to	1850	Shale and shells
1850	to	2025	Red bed and shale
2025	to	2065	Anhydrite
2065	to	2635	Shale and shells
2635	to	2820	Shale
2820	to	2925	Lime and shale
2925	to	2990	Shale and lime
2990	to	3070	Lime and shale
3070	to	3160	Shale and lime
3160	to	3535	Lime and shale
3535	to	3735	Lime
3735	to	3772	Lime and shale
3772	to	3775	Lime
3775			R.T.D.

Set 258' of 8-5/8" Surface Casing, cemented with 125 sacks of cement.

ELEVATION: ~~3438~~<sup>2449</sup> KB Est.

TOPS: Heebner 3482'; Toronto 3504'; L.S. K.C. 3522'; Base of K.C. 3702'; Arbuckle 3772'; R.T.D. 3775'.  
3703

Set 3774' - 5 $\frac{1}{2}$ " Casing - cemented with 100 sacks of cement.

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the LAWSON #5, CWL SE $\frac{1}{4}$  of Section 36-Township 3-Range 24 West, Norton County, Kansas, as reflected by the files of the Empire Drilling Company.

*Dan J. Kornfeld*  
Dan J. Kornfeld  
STATE CORPORATION COMMISSION  
RECEIVED  
MAR 1954

Subscribed and sworn to before me a Notary Public within and for Sedgwick County, Kansas, this 15th day of February 1954.

*Mary Heininger*  
NOTARY PUBLIC

My Commission Expires May 5, 1956