


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-137-00627-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Norton County, Sec. 35 Twp. 3 Rge. 24 (E) (W)<sup>X</sup>  
Location as "NE/CNW/SW" or footage from lines. SW SE NW  
Lease Owner R. P. Nixon  
Lease Name Henry Well No. 3  
Office Address 754 E. Wichita Ave., Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 12-6 1959  
Application for plugging filed 12-14 1959  
Application for plugging approved 12-15 1959  
Plugging commenced 12-16 1959  
Plugging completed 12-23 1959  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		3279.32'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled 4 1/2" with sand from 3714 to 3680 dump 2 sacks of cement with dump baler. Shot pipe loose at 3270.  
Pulled pipe out, mudded up to 360 ft., 10 ft rock bridge.  
Dump 20 sacks cement mud up to 40 ft., 5 ft. rock bridge  
dump 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Arnett Casing Pulling Company  
Address 172 West 3rd, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
R. P. Nixon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
754 E. Wichita Avenue, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 60

My commission expires 12-9-63  
[Signature] Notary Public.



15-17-00627-00-00

# DRILLER'S WELL LOG

OPERATOR: R. P. NIXON  
Russell, Kansas

WELL NAME: #3 HENRY  
LOCATION: SW SE NW  
Sec. 35-3S-24W  
NORTON CO, KANSAS

CONTRACTOR: K & E DRILLING, INC.  
719 UNION CENTER BLDG.  
WICHITA, KANSAS

COMMENCED: 12-1-59

CASING RECORD: 8-5/8" @ 364' (200 sx cmt)  
4-1/2" @ 3714' (100 sx cmt)

COMPLETED: 12-6-59

ELEVATION: 2374' KB

ROTARY TOTAL DEPTH: 3715'

PRODUCTION: unknown

## FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Cellar (soil & clay)	8
Soil & Clay	65
Shale	890
Shale & Sand	1050
Sand, Rock & Shale	1180
Shale & Sand	1270
Shale	1600
Sand	1695
Red Bed	1945
Anhydrite	1975
Shale & Shells	2450
Lime & Shale	2900
Lime	2995
Lime & Shale	3365
Lime	3645
Lime & Shale	3695
Lime	3715
R.T.D.	3715'



## CERTIFICATION

State of KANSAS }  
County of SEDGWICK } ss:

I, Dale Silcott of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*Dale Silcott*  
Dale Silcott

Subscribed and sworn to before me this 14 day of December, 19 59.

*Patricia M. Edwards*  
Patricia M. Edwards, Notary Public.

My Commission expires August 11th, 1962.

RECEIVED  
STATE CORPORATIONS COMMISSION  
JAN 12 1960  
1-12-60  
CONSERVATION DIVISION  
Wichita, Kansas

