

15-137-19013-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Norton County, Sec. 35 Twp. 3 Rge. (E) 24(W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SW
Lease Owner **Harry Gore**
Lease Name **Henry** Well No. **1**
Office Address **400 Brown Building, Wichita, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **dry hole**
Date well completed **4-22-54** 19.
Application for plugging filed **5-10-54** 19.
Application for plugging approved **5-11-54** 19.
Plugging commenced **5-11-54** 19.
Plugging completed **5-20-54** 19.
Reason for abandonment of well or producing formation **dry hole**

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **yes**

Name of Conservation Agent who supervised plugging of this well **Eldon Petty**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **3753** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	263	
				5-1/2	3,747	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3754 to 3730 ft.	Sand bridge
3730 to 3710	4 sks. cement
3710 to 270	mudded
270 to 255	rock bridge
255 to 210	15 sks. cement
210 to 30	Mud
30 to cellar	10 sks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor **R & S Pipe Pulling Co.**
Address **Box 192, Ellinwood, Kansas**

STATE OF **Kansas** COUNTY OF **Sedgwick**, ss.
Theodore Gore (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Theodore Gore*
400 Brown Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this **8th** day of **June**, 19**54**

My commission expires **June 7, 1956**

Charlotte Ketchka
Notary Public.

PLUGGING
FILE SEC. 35 T. 3 R. 24W
BOOK PAGE 33 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 - 1954
CONSERVATION DIVISION
Wichita, Kansas

15-137-19013-00-00


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY HARRY GORE
FARM Henry NO. 1

SEC. 35 T. 3 R. 24W
LOC. SE NE SW

TOTAL DEPTH 3750
COMM. 4-13-54 COMP. 4-22-54
SHOT OR TREATED
CONTRACTOR Empire Drilg. Co.
ISSUED

COUNTY Norton



CASING
20 10
15 8 5/8 " 263' w/125 sx cem.
12 6
13 5 1/2 " 3747 1/2' w/100 sx cem.

ELEVATION 2423 K B

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

surface hole	282
shale & shells	1998
anhydrite	2030 2024
red bed, shale & shells	2255
sh ale & shells	2585
brown lime & shale	2765
shale & lime	2870
shale & shells	2965
shale & lime	3153
shale & shells	3255
lime & shale	3481
lime	3740
shale	2746
sand	3750
TOTAL Depth sand	3757
Total Depth	
TOPS:	
Heebner	3443
Toronto	3470
Lansing-Kansas City	3481
Base Kansas City	3666
Reagan sand	3746
Top Granite	3753

PLUGGING
FILE SEC. 35 T. 3 R. 24W
BOOK PAGE 33 LINE 22

RECEIVED
COMMISSION
JUN 7 1954
CONSERVATION DIVISION
Wichita, Kansas