

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - D39 - 20370-00-00 (of this well)
Lease Owner Bolyard Oil & Gas, Ltd.
Address Brooks Tower, Suite 20C, 1020 15th St., Denver, Colorado 80202
Lease (Farm Name) CECIL Well No. 1
Well Location C SW NW Sec. 30 Twp. 3S Rge. X(E) 26W (W)
County Decatur Total Depth 4060' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 7:45 p.m. 1-11-77

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 South 2nd, Hill City, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Bolyard Oil & Gas, Ltd., Brooks Towers, Suite 20C, Denver, Colorado 80202

Address " " "

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Date: January 14, 1977

RECEIVED
JAN 21 1977
CONSERVATION
Wichita, Kans.

1-21-77

15-039-20370-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Bolyard Oil & Gas, Ltd.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: CECIL #1
 LOCATION: C SW NW, Section 30-3S-26W
 Decatur County, Kansas
 SPUD DATE: 1-03-77
 COMPLETION DATE: 1-11-77

0	135	Clay & Sand
135	180	Sand
180	1230	Shale
1230	1300	Sand
1300	1875	Shale
1875	2230	Sand
2230	2796	Shale
2796	3634	Lime & Shale
3634	3693	Lime
3693	3760	Lime & Shale
3760	4060	Lime
	4060	Rotary Total Depth

Drilled 258' of 12 3/4" hole. Ran 6 jts. of used 8 5/8" - 28# Casing. (Tally 248.64')
 Set at 258' K.B. Cemented with 180 sx. common cement, 2% gel, 3% Ca. Cl. Cement did
 circulate. Job complete at 8:30 p.m. 1-03-77.

T.D. 4060', Set 1st plug at 1200' with 70 sx., 2nd plug at 200' with 20 sx., 40' bride
 with 10 sx. Job was complete at 7:45 p.m. 1-11-77. Cement by Halliburton.

SAMPLE TOPS:

Anhydrite 2197'
 B/Anhydrite 2230'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECORDED
 JAN 21 1977
 1-21-77
 COUNTY OF SEDGWICK
 MISSOURI


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby
 state that the above and foregoing is a true and correct log of the CECIL #1, C SW NW,
 Section 30-3S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and
 state as of this 14th day of January, 1977.

Kathy S. Goertz
 Kathy S. Goertz, Notary Public



State of Kansas



15-039-20370-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 13, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Cecil
Description	C SW NW Sec. 30-3-26W
County	Decatur
Total Depth	4060
Plugging Contractor	Abercrombie Drilling Co., Inc


Bolyard Oil & Gas, Ltd.
1020 15th Street, Suite 20-C
Denver, Colorado 80202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above named well.