

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

130 S. Market, Room 2078  
Wichita, Kansas 67202

RECEIVED  
APR 19 2004  
KCC WICHITA

FORM CP-1

Rev. 03/92

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 047 15-083-21486-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation  
(owner/company name)

KCC LICENSE # 5003  
(operator's)

ADDRESS: 8080 E. Central CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737

LEASE: McAvoy 'A' WELL#: 1-18 Section 18 Township 23s Range 20w

NE  
No

Se Sw Ne SPOT LOCATION/QQQQ COUNTY: Edwards

2145 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

1485 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_

CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 554' KB CEMENTED WITH 265 SACKS

PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATIO 2328 G.L. 2337 K.B. T.D. 4800 PBDT \_\_\_\_\_ Anhydrite Depth 1500-1525  
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:

Received plugging orders 04/09/04 (Mike Meier). Plugging began at 11:00 am 4/12/04. Heavy mud in hole and between all plugs. Plugged using 155 sx 60/40 Poz and 1/4 lb/sx Cellflake. Bottom plug at 1500'; 50 sx, 2nd plug at 600'; 80sx, top plug at 40'; 10sx. Rathole 10 sx. No Mousehole. Job finished at 1:45 pm 04/12/04. Acid Services ticket #8253. Top plug fell down to ~150'. On 04/14/04 top of fluid at 150'. Cemented thru 2" to top of casing with 53sx 60/40 Poz; 6% Gel. 3 bbl circulated to cellar. Complete at 9:30 am. Acid Services ticket #8282.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lanny Saloga/Gary M. Talbott Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142  
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 1:45 pm on April 12, 2004. Cemented top again on 04/14/04. 9:30 am.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 04/12/04 AUTHORIZED OPERATOR OR AGENT:

Plugged  
Gary M. Talbott  
(signature) Gary M. Talbott, Agent for Operator

