

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

15-137-20231-00-00

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

API NUMBER 15-137-20,231 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER Thunderbird Drilling, Inc.

ADDRESS P.O. Box 18407- Wichita, Kansas 67218

LEASE (FARM NAME) Brooks WELL NO. 2

WELL LOCATION SE SW SEC. 33 TWP. 3S RGE. 25W (EAST) (WEST)

COUNTY Norton TOTAL DEPTH 4050 FIELD NAME _____

OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? yes
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 A.M. 7/3/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

E.R. Cook ADDRESS P.O. Box 864- Great Bend, Ks. 67530

PLUGGING CONTRACTOR Thunderbird Drilling, Inc. LICENSE NO. _____

ADDRESS Same as above

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Thunderbird Drilling, Inc.

ADDRESS Same

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OF ACTING AGENT.

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1981
08-07-1981
CONSERVATION DIVISION
Wichita, Kansas

SIGNED: *E.R. Cook*
APPLICANT OR ACTING AGENT

DATE: 8/6/81

KANSAS DRILLERS LOG

API No. 15 — 137 — 20,231-00-00
County Number

S. 33 T. 3S R. 25W E
W

Loc. SE SW

County Norton

Operator
Thunderbird Drilling, Inc.

Address
 P.O. Box 18407- Wichita, Kansas 67218


Well No. 2 Lease Name Brooks

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Thunderbird Drilling, Inc. Geologist Paul Montoia

Spud Date 6/24/81 Total Depth 4050 P.B.T.D.

Date Completed 7/3/81 Oil Purchaser



Locate well correctly
 Elev.: Gr. 2477

DF _____ KB 2482

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4	8 5/8"	24#	263'	com	190	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 7 1981
 CONSERVATION DIVISION
 Wichita Kansas

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
Disposition of gas (vented, used on lease or sold)	bbls.	MCF	bbls.	CFPB	
Producing interval (s)					

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Thunderbird Drilling, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

2

Lease Name

Brooks

Dry Hole

S 33 T 3S R 25W E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 /30-30-30-30, rec.120' vhospm, 867' wnm w/ssg, FP 98-375#, BHP 1159-1140#	3406	3475	Sample Anhydrite B/Anhydrite	2071+ 411 2106+ 376
DST #2 /60-60-15-30, rec. 35' sosm, 62' nmw, FP 59-98#, BHP 1159-1081#	3489	3540	Log Topeka	3470- 788
DST #3 /45-45-45-45, rec. 15' osm, FP 69-59# BHP 59-59#	3550	3620	Heebner Lansing BKC	3476- 974 3520-1038 3714-1232
DST #4 /15-30-15-30, rec. 5' osm, FP 29-29# BHP 39-19#	3612	3649	Arbuckle Reag. Sd. Granite Wash RTD LTD	3856-1374 4010-1528 4034-1552 4050-1568 4051-1569
<u>From</u> <u>To</u> <u>Description</u>				
0	263'	Surface hole		
263	1726	Shale		
1726	1844	Sand		
1844	2071	Sand & Shale		
2071	2106	Anhydrite		
2106	2690	Shale		
2690	3255	Shale & Lime		
3255	3540	Lime		
3540	3618	Shale & Lime		
3618	4050	Lime		
4050	R.T.D.			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

[Handwritten Signature]

Signature

Vice-President

Title

August 6, 1981

Date

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

August 26, 1981

INVOICE NUMBER: 6322-W

TO: Thunderbird Drilling, Inc.
P.O. Box 18407
Wichita, KS., 67218

15-137-20231-00-00

PLUGGING ASSESSMENT AS FOLLOWS:

PAYABLE UPON RECEIPT

Brooks #2
Se SW, Sec. 33-38-25W
Norton
Thunderbird Drilling, Inc.
T. D. 4050'

\$131.63

NOTE: We also need the following before our file is completed:

- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

For Administrator



Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS., 67601

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE