

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUL 19 2004

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399 Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: ENHR Oil Docket #: NA (If SWD or ENHR)

The plugging proposal was approved on: 6/30/04 7/13/04 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing KC Depth to Top: 3102' Bottom: 3224' T.D. 3280'

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D. 3320'

API Number: 15-009-30289-00-00

Lease Name: Kraft-Prusa UT KCC BEM 8-8 8/19/04

Well Number: 8-8

Spot Location (QQQQ): C - NW - SE - NE

3630' Feet from North / South Section Line

990' Feet from East / West Section Line

Sec. 13 Twp. 17 S. R. 11 East West

County: Barton

Date Well Completed: 5/6/65

Plugging Commenced: 7/12/04

Plugging Completed: 7/12/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Lansing/KC with Oil content and casing sizes 85/8 and 41/2.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Mixed 150sx cement with 500# hulls and pumped down 41/2 casing cir up 85/8 with 60 bbl out, Shut back side in and pumped 23 bbl. Mixed 10sx and squeezed to 400# shutin.

Name of Plugging Contractor: Swift Services Inc. License #: 32382

Address: P.O. Box 466 Ness City Ks. 67560


Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 399 Garden City Ks. 67846



SUBSCRIBED and SWORN TO before me this 14 day of July, 2004

[Handwritten Signature] My Commission Expires: 11/4/07 Notary Public