

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUL 23 2004

KCC WICHITA

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: RUPE OIL COMPANY, INC.
Address: P.O. Box 783010 Wichita, Kansas 67278
Phone: (316) 689-352- Operator License #: 5047
Type of Well: oil gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. 2672'

API Number: 15 - 053-20,509 -00 -00
Lease Name: Alden
Well Number: 2
Spot Location (QQQQ): _____ - SE - SE - SE
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 30 Twp. 15 S. R. 8 East West
County: Ellsworth
Date Well Completed: 1978 *KCC BEW 8-19-04*
Plugging Commenced: ~~6-30-04~~ 7-2-04
Plugging Completed: 7-2-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	230'	None
				4-1/2"	2668'	1618'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2550' and 4 sacks cement. Cut 4-1/2" casing loose @1618', pulled up to 900', pumped 35 sacks cement with 200# hulls, pulled up to 600', pumped 35 sacks cement with 100# hulls, pulled up to 290' and circulated cement to surface. 60/40 pos. 4% gel.
Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Rupe Oil Company, Inc.
State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 22nd. day of July

Irene Herzberg
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202