

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15 195-22,252-00-00

LEASE NAME Keller-Keller

WELL NUMBER 1-16

2590 Ft. from S Section Line

4310 Ft. from E Section Line

SEC. 16 TWP. 13S RGE. 21W (E) or (W)

COUNTY Trego

Date Well Completed 5/21/04

Plugging Commenced 11:00AM 5/21/04

Plugging Completed 1:00PM 5/21/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DOWNING-NELSON OIL CO., INC.

ADDRESS P.O. Box 372 Hays, KS 67601

PHONE# (785)628-3449 OPERATORS LICENSE NO. 30717

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/20/04 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.O. 4008

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	222	8 5/8	222.42	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
1st Plug @ 1625'w/25sks 10sks In Mouse Hole Circulated 1st Plug 30minutes w/52 Vis Mud
2nd Plug @ 875'w/100sks 15sks In Rat Hole Plugs displaced with mud.
3rd Plug @ 275'w/40sks Total 200sks 60/40Poz 6%Gel w/1#CF/sk By Allied Cementing
4th Plug @ 40'w/10sks Completed @ 1:00PM 5/21/04

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DOWNING-NELSON OIL CO., INC.

STATE OF Kansas COUNTY OF ELLIS, ss.

Ron Nelson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ron Nelson

(Address) 3322 Lincoln Hays, ks

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 192004

Chris Schneider
Notary Public

My Commission Expires: 8-20-07

RECEIVED

AUG 18 2004

KCC WICHITA

Form CP-1
Revised 05-88

CHRIS SCHNEIDER
Notary Public - State of Kansas
My Appt. Expires 8-20-07

[Handwritten signature]