

STATE OF KANSAS
STATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-009-24492 -00-00

LEASE NAME Dannebohm

WELL NUMBER 1

1480 Ft. from ^{S. 1/4} Section Line

4620 Ft. from ^{E. 1/4} Section Line

SEC. 36 TWP. 20 RGE. 12W (E) or (W) 7-27-04

COUNTY Barton

Date Well Completed

Plugging Commenced 4-23-04

Plugging Completed 4-26-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CASINO PETROLEUM

ADDRESS P.O. Box 415 Ellinwood, Kansas 67530

PHONE (620) 564-2517 OPERATORS LICENSE NO. 4184

Character of Well Oil EOR E26516.1

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Patrick Staab (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>			<u>268</u>	8-5/8"	268'	None
<u>Prod</u>			<u>3459</u>	4-1/2"	3459'	2013'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3200' and 4 sacks cement. Cut pipe loose @2013', pulled up to 1450', pumped 70 sacks cement with 100# hulls, pulled up to 600', pumped 80 sacks cement with 100# hulls, pulled up to 300' and circulated 50 sacks cement to surface. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Casino Petroleum

State of Kansas County of Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

I, above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524


RECEIVED

MAY 10 2004

KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 7th day of May, 2004

My Commission Expires:



Notary Public

Form 05-
Revised 05-