


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Norton County, Sec. 24 Twp. 3S Rge. (E) 25(W)
Location as "NE/CNW/SW" or footage from lines SW NE

Lease Owner Arvel C. Smith
Lease Name Juenemann Well No. 1
Office Address 534 N. Tallyrand, Wichita 6, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 21, 1964
Application for plugging filed 19 64
Application for plugging approved 19 64
Plugging commenced 19 64
Plugging completed 19 64
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3724 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0	234'	7"		No

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0' - 40' Six Sack Cement Plug
40' - 170' Heavy Mud
170' - 230' Fourteen Sack Cement Plug
230' - 530' Heavy Mud
530' - 600' Fourteen Sack Cement Plug
600' - Total Depth Heavy Mud

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1964
06-02-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Co.
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Arvel C. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arvel C. Smith
Arvel C. Smith
534 N. Tallyrand, Wichita 6, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 19 64

My commission expires Dec 29, 1964

Petty Lee Hallmark
Notary Public.



ARVEL C. SMITH
534 TALLYRAND
WICHITA 6, KANSAS

MURRAY 6-0502

15-137-00283-00-00

June 1, 1964

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1964
06-02-1964
CONSERVATION DIVISION
Wichita, Kansas

Erroneously filed by Sterling
Drilling Co. as "Ben J. Taylor".


Arvel C. Smith

24-3-25W

15-137-00283-00-00

STERLING DRILLING COMPANY

Sterling, Kansas

WELL LOG ----- Juenemann #1

LOCATED: SW NE Section 24-3S-25W, Norton County, Kansas

Arvel C. Smith

OWNER: ~~Ben J. Taylor~~

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 15, 1964

COMPLETED: May 21, 1964

ROTARY TOTAL DEPTH: 3720'

LOG

0 - 130	Clay & Sand
130 - 360	Shale
360 - 1840	Sand & Shale
1840 - 1943	Shale
1943 - 1973	Anhydrite
1973 - 2555	Shale
2555 - 3720	Shale & Lime TD

CASING RECORD

Ran 229.43' of 7" casing, set at 242' with 175 sacks of Pozmix with HA-5.

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1964
05-27-1964
CONSERVATION DIVISION
Wichita, Kansas