

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20148-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1970
CONSERVATION DIVISION
Wichita, Kansas
3-20-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Consolidated Oil & Gas, Inc., & John O. Farmer, Inc.,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Montgomery Well No. B-1

Location NE-NE-NE Sec. 17 Twp. 3 Rge. (E) (W) 26

County Decatur Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address 370 West Wichita Avenue, Russell, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 14 Month 3 Year 1970

The above well was plugged as follows:

236'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement
thru DP. Pulled DP to 240' and displaced 20 Sx. cement thru DP. Pulled DP,, set
bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 3/20/70
INV. NO. 1618-W