

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1969
CONSERVATION DIVISION
Wichita, Kansas
2-24-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20077-00-00

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name W. L. Hix Well No. 1

Location NW-SE Sec. 5 Twp. 3 Rge. (E) (W) 26

County Decatur Total Depth 3454

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kans. License No.

Operation Completed: Hour 11:00AM Day 21 Month 2 Year 1969

The Above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota Section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1475' and displaced 100 Sx. cement thru
DP from 1475' to 1150'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275 to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Roberts
Well Plugging Supervisor

DATE 2/25/69

INV. NO. 9373-4