

91

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-137-30008-00-00

JUL 6 1965
07-06-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tom-Kat, Incorporated,

Complete Address: 1125 Wichita Plaza Building, Wichita, Kansas.

Lease Name Schoen Well No. 1

Location CSW-NW Sec. 23 Twp. 3 Rge. (E) (W) 25

County Norton Total Depth 3810

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 1:00PM Day 29 Month 6 Year 1965

The Above well was plugged as follows:

244'--8.5/8" Surface pipe, cement circulated with 175 Sx.
Circulated hole with heavy mud, set plug @ 600' and 20 Sx. cement displaced
at thru DP. Heavy mud to 240', set plug with 1/2 sack hulls and displaced 20
Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7-6-65

INV. NO. 1415-W