

KANSAS ^R
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-137-00040-00-02

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1965
67-08-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tom-Kat, Incorporated,

Complete Address: 1125 Wichita Plaza Building, Wichita, Kansas.

Lease Name Mizell Well No. 1

Location NE-NE-SE Sec. 15 Twp. 3 Rge. (E) (W) 25

County Norton Total Depth 3897

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This well was a WASHDOWN

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 12:00M Day 2 Month 7 Year 1965

The Above well was plugged as follows:

297'--8 5/8" Surface pipe, cement circulated. 6 3/4" hole to TD.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 290', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-8-65

INV. NO. 1433-W

Signed: W. L. Nichols
Well Plugging Supervisor