

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-17-1968
DEC 17 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20020-00-00

Operator's Full Name Ferguson Oil Company,

Complete Address: 1115--100 Park Avenue Building, Oklahoma City, Oklahoma. 73102

Lease Name Browne Well No. 1

Location NE-SW Sec. 11 Twp. 3 Rge. (E) (W) 25

County Norton Total Depth 3775'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kans. License No.

Operation Completed: Hour 3:00 PM Day 13 Month 12 Year 1968

The Above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 935'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 825'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from 275'
to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Doherty
Well Plugging Supervisor

DATE 12/17/68
INV. NO. 9032-u