

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-137-00116-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW NW

SEC. 10 TWP. 3RGE. 25 W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Mizell

Operator R. H. Shields Address 1307 Sharp Bldg Lincoln, Neb

Field _____ County Norton

Total Depth 3902 Feet.

Plugging Contractor Bert Self Pipe Plling Co

Plugging Contractor's License No. 48

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 231' circulated with cement - 5 1/2" at 3712 with

175 sax cement - Lane Wells plugs at 3540 - squeezed at 3558'

with 200 sax cement - perforated at 3517'

Filled with chat to 3500', set 4 sax cement with dump bailer,

pulled 3500' 5 1/2", mud to 250', set rock and 25 sax cement, mud

to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 10 T 3 R 25 W
BOOK PAGE 24 LINE 28

RECEIVED
STATE COMMISSION
APR 2 1954
04-02-1954
CONSERVATION DIVISION
Wichita, Kansas

E. J. Terry
District Conservation Agent
Date 3-31-54