

15-137 20014-00-00

KANSAS

Form CP-3  
Rev. 6-9-67

*3*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
04-08-1968  
APR 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rocket-Schusterman Oil A/C,  
Complete Address 1209 Mid-Continent Building, Tulsa, Oklahoma.  
Lease Name Wiltfong Well No. 1  
Location NE-NE-SW Sec. 12 Twp. 3 Rge. (E) (W) 25  
County Norton Total Depth 3785  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center, Wichita, Kansas. License No.         
Operation Completed: Hour 8:00 AM Day 4 Month 4 Year 1968

The above well was plugged as follows:

261'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Top of Nakota section @ 1000'.  
Circulated hole with heavy mud. Pulled DP to 1210' and displaced 100 Sx. cement  
thru DP from 1210' to 885'. Pulled DP to 275' and displaced 20 Sx. cement thru DP  
from 275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar. (Cementing operations performed by Halliburton Company).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 4/8/68  
INV. NO. 7537-W