

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-37-30004-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1965
04-26-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sauvage Drilling Company,

Complete Address: Oberlin, Kansas.

Lease Name Collins Well No. 1

Location SW-SE Sec. 11 Twp. 3 Rge. (E) (W) 25

County Norton Total Depth 3773

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 3:30PM Day 19 Month 4 Year 1965

The Above well was plugged as follows:

265'--8 5/8" Surface pipe, cement circulated with 170 Sx.

LAND OWNER REQUESTED WELL BE LEFT AS IRRIGATION WELL.

Circulated hole with heavy mud, set plug @ 540' and displaced 15 Sx. cement

thru DP. Heavy mud to 290', set plug with $\frac{1}{2}$ sack hulls and ran 15 Sx.

cement thru DP. Top cement plug displacement from 290' to 250'.

Hole left open from 250 to surface. (Authorization Attached)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/26/65
INV. NO. 1042-W

Signed: N. L. Nichols
Well Plugging Supervisor