

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20254-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1973

CONSERVATION DIVISION  
Wichita, Kansas

1-30-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Buttes Gas and Oil Company,

Complete Address 1776 Lincoln Street, Denver, Colorado.

Lease Name Brown Estate Well No. 1

Location CNE-SE Sec. 21 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3825'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 11:45 PM Day 28 Month 1 Year 1973

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement  
thru DP from 1500' to 1175'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dehals  
Well Plugging Supervisor

INVOICED

DATE 1/30/73  
INV. NO. 6921-W