

KANSAS

Form CP-3
Rev. 6-9-67

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1967
10-19-67
CONSERVATION DIVISION
WICHITA, KANSAS

15-039-20024-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Delbert Well No. 1

Location NE-NE-SE Sec. 15 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3840'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 8:30PM Day 10 Month 10 Year 1967

The above well was plugged as follows:

254'--8 5/8" Surface pipe, cement circulated with 215 Sx.
Dakota section from 1200' to 1375'.

Checked fluid level in hole, found it @ 620'. Ran DP to 150' and attempted to balance plug using 20 Sx. cement plus 6% gel and 4% Ca Cl/2. After 3 hours ran DP back in hole to feel for plug but it had gone down the hole. Tried the second time to balance plug @ 1750' with no success. Made wooden bridging plug and pushed to 1400' with DP then pulled DP and ran 1 yard crushed rock on top of bridging plug. Ran DP to top of crushed rock @ 1325' and displaced 60 Sx. cement plus 6% gel thru DP from 1325' to 1090'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240' to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.
(Cementing operations performed by Sun Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*
Well Plugging Supervisor

DATE 10/19/67

INV. NO. 6518-W