

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas
8-10-70

15-039-20169-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Adair Oil, Slawson Drilling and Pickrell Drilling Co.,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Kolsky Well No. A-1

Location NW-SW-SW Sec. 13 Twp. 3 Rge. (E) (W) 27

County Decatur Total Depth 3805'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Slawson Drilling Company, Incorporated.

Address 408 One-Twenty Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:15 AM Day 6 Month 8 Year 1970

The above well was plugged as follows:

265'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 280' and displaced 20 Sx. cement thru DP from
280' to 220'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Dechals
Well Plugging Supervisor

DATE 8/10/70

INV. NO. 2347-W