

State of Kansas



15-039-20077-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 24 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 2-24-69

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name: W. L. Hix Well No. 1

Location: NW-SE Sec. 5 Twp. 3 Rge. (E)(W) 26

County: Decatur Total Depth 3454' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

251'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1475' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*M. L. Pichok*  
 Conservation Division Agent