



15-039-20148-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1970
CONSERVATION DIVISION
Wichita, Kansas
3-20-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated, has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated, & Consolidated Oil & Gas, Inc.,

Complete Address: 370 W. Wichita Avenue, Russell, Kansas.

Lease Name: Montgomery Well No. B-1

Location: NE-NE-NE Sec. 17 Twp. 3 Rge. (E)(W) 26

County: Decatur Total Depth 3720' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

236'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1125.

Circulate hole with heavy mud. Pull DP to 1350' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent