

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-137-30085-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1966  
12-20-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. L. D. Carson of Lario Oil & Gas Company has this  
date requested permission to plug the following described well:

Mr. Carson guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company,

Complete Address: 301 South Market, Wichita, Kansas.

Lease Name: Alvin Schoen Well No. 1

Location: CSW-NW Sec. 16 Twp. 3 Rge. (E)(W)25

County Norton Total Depth 3890' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Carson was instructed to plug the well as follows:

300'--8 5/8" Surface pipe, cement circulated with 215 Sx.

Circulate hole with heavy mud, set plug @ 600' and 25 Sx. cement.

" " 300' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

W. L. Mitchell  
Conservation Division Agent