



15-039-20254-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1973

CONSERVATION DIVISION  
Wichita, Kansas

1-30-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this  
date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Buttes Gas and Oil Company,

Complete Address: 1776 Lincoln Street, Denver, Colorado.

Lease Name: Brown Estate Well No. 1

Location: CNE-SE Sec. 21 Twp. 3 Rge. (E)(W) 27

County: Decatur Total Depth 3825' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1275'

Circulate hole with heavy mud. Pull DP to 1500' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Dickale  
Conservation Division Agent