



15-039-20253-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1973
CONSERVATION DIVISION
Wichita, Kansas
1-2-73

Dear Sir:

Mr. Ralph Nierenberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Nierenberger guarantees payment of the plugging fee,

Operator's full Name: Buttes Gas & Oil Company.

Complete Address: 1776 Lincoln, Denver, Colorado.

Lease Name: M. H. Shirley Well No. 1

Location: CSW-NE Sec. 11 Twp. 3 Rge. (E)(W) 27

County: Decatur Total Depth 3865' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nierenberger was instructed to plug the well as follows:

273'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1475' and displace 110 Cu. Ft.
Cement thru DP. Pull DP to 290' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

M. L. D. J. J. J.
Conservation Division Agent