



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-20236-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 1974

CONSERVATION DIVISION
Wichita, Kansas

3-6-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of SW Casing Pulling Co., Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Gillespie Well No. 2

Location: CSE-SE Sec. 10 Twp. 3 Rge. (E)(W) 27

County: Decatur Total Depth 3840' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

266'--8 5/8" Surface casing, cement circulated with 200 Sx.
3839'--5 1/2" Production casing cemented on bottom with 150 Sx. Well
plugged back to 3660'. Top perforations from 3634' to 3636'. Top of
cement @ 3216'.

Sand well back to 3600' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

Conservation Division Agent